



Mountain Division Rail Corridor
Interim Trail – Standish to Fryeburg
Planning Feasibility Study
WIN 026858.00

Dakota Hewlett
MaineDOT Project Manager


Lori Driscoll, P.E.
HNTB Project Manager

PROJECT DESCRIPTION

- Feasibility Study to investigate converting a 31-mile section of the inactive Mountain Division Rail Corridor to an interim use off road shared-use path/trail.
- The report covers:
 - technical aspects of the trail design
 - condition of the existing bridge structures
 - trail alternatives through Portland Water District's (PWD) property
 - evaluation of possible trail segments and sequence of construction

PROJECT LOCATION AND LIMITS

Generally, following the Mountain Division Rail Corridor from Route 35 (near Johnson Field) in Standish, through Baldwin, Hiram, Brownfield and ending at Route 113 in Fryeburg.



PROJECT HISTORY

- In 2007 HNTB Corporation authored a report for the MaineDOT Office of Freight Transportation.
- The purpose of the report was to investigate the viability of utilizing the Mountain Division Rail Corridor for the following potential uses:
 - local freight service
 - commuter service to Portland
 - tourist and excursion service
 - combination of some of the above
- The report concluded that passenger rail was not feasible, and freight rail was only feasible under ideal conditions.



PROJECT HISTORY


In March 2021, Legislative Documents LD 672 and LD 1133 created a Rail Use Advisory Council (RUAC) to evaluate the feasibility of three potential uses of 31-miles of the inactive Mountain Division Rail Corridor:

1. Rail
2. Trail only on the existing rail bed
3. Rail with an adjacent trail

2022 Feasibility Study conducted by HNTB Corporation, resulted in the RUAC voting for Option 2 Trail Only on the existing rail bed. Per LD 1133 any non-rail use of the Mountain Division corridor will be considered *interim in nature* and the corridor must be preserved for future rail use.

TECHNICAL ASPECTS – Typical Section

- The Shared Use Path (SUP) will be 10' wide with 2' grass shoulders.
- In areas of steep sideslopes, there will be a fence or some sort of barrier within the 2' grass shoulder.



TECHNICAL ASPECTS – Typical Section

- The railroad ties are in poor condition and would need to be replaced if train operation resumes, therefore the ties and rails will be removed (except on bridge structures) before path construction.
- The ballast will remain in place and will provide a solid base for the path. The path will be constructed approximately six inches above the existing ballast elevation. Aggregate subbase gravel will be placed over the ballast to achieve the increased height.
- The path surface will be paved or stone dust for a surface treatment.
- On bridge structures, the ties in poor condition will be replaced to accommodate timber bridge decking.

TECHNICAL ASPECTS – Alignment

- The path is proposed to be constructed on the existing rail bed (except for the path segment through PWD's property in Standish).
- The proposed profile will generally follow the profile of the existing rail corridor which is generally flat.
- The steepest grade on the corridor is 1.6%, flatter than the maximum grade suggested for bicycle facilities.



TECHNICAL ASPECTS – At Grade Road Crossings

- The path will cross 25 roadways at grade along the 31-mile corridor.
- Each crossing will be evaluated individually during design for sight distance.



TECHNICAL ASPECTS – Structures

- 13 numbered railroad bridge structures with spans of nine (9) feet and longer.
- Inspected every five (5) years since the railroad corridor is inactive.
- A desktop review of bridge inspection reports and a site visit were conducted to evaluate repair needs and costs.



TECHNICAL ASPECTS – Structures

Repairs will include:


- Replacement of structurally deficient railroad ties
- Conversion of the open tie deck to closed decks with timber rail
- Repair of substructures that are exhibiting stability loss or undermining



TECHNICAL ASPECTS – Structures

Proposed Bridges:

- Design loads for a pedestrian bridge are much less than for a railroad bridge
- Selective replacement of timber ties (based on condition) before adding decking




TECHNICAL ASPECTS – Structures

- 15 granite box culvert structures with individual spans of six (6) feet and shorter. Some are multi-cell with a total width exceeding six (6) feet
- Repairs are recommended only when necessitated by condition





PORTLAND WATER DISTRICT (PWD) STUDY AREA

- Mountain Division Rail Corridor passes through Portland Water District property along south end of the project in Standish
- Due to public water supply, PWD restricts recreational activity near Sebago Lake
- Due to the rail corridor's proximity to the lake, it cannot be used as a shared-use path in this area
- MaineDOT does not have property rights for a trail in this section.



PWD STUDY AREA – Alignment Alternatives

- Three possible path alternatives were investigated as shown on the graphic.




PWD STUDY AREA – Alternative 1

- Trail length: ~3.5 Miles
- 32% of the trail is located along existing roadways adjacent to, but separated from, traffic
- Remaining 68% is through wooded areas within PWD property
- Large culverts at Sticky River and Smith Mill Rd. will need to be lengthened to accommodate the path
- ROW impacts are likely



PWD STUDY AREA – Alternative 2

- Trail length: ~2.6 Miles
- 16% of the trail is located along existing roadways adjacent to, but separated from, traffic
- Remaining 84% is through wooded areas within PWD property
- Path remains within PWD property
- New water crossing west of existing railroad crossing



PWD STUDY AREA – Alternative 3

- Trail length: ~3.8 Miles
- 100% of the trail is located along existing roadways adjacent to, but separated from, traffic
- Large culverts at Sticky River and Smith Mill Rd. will need to be lengthened to accommodate the path
- ROW impacts are likely



PWD STUDY AREA - Recommended Alternative

Alternative 1 is recommended for the following reasons:

- Most cost-effective option
- Least number of environmental impacts
(Alternative 2 would be difficult to permit due to new water crossing)
- Improved safety over Alternative 3
(Fewer roadway crossings, and the path is adjacent to traffic, only where necessary, at water crossings)




PROJECT SEGMENTS– Trailhead Locations

- Constructing 31 miles of path under a single construction project is likely not feasible, therefore dividing the project into smaller segments was investigated.
- Each segment needs a logical begin and end that is accessible by the public.
- Four potential trailhead locations have been identified and are listed from north to south:
 1. Hiram - adjacent to rail corridor off Mountain View Ave.
 2. West Baldwin – former Cornish Station
 3. Baldwin – near the Whistle Stop General Store
 4. Standish – old track siding off Route 114 near Cole Hill Road

PROJECT SEGMENTS

Six segments are proposed as shown in different colors on the graphic to the right. Segment 1 starts at the existing Mountain Division Trailhead in Fryeburg and Segment 6 ends at Johnson Field in Standish.



CONSTRUCTION SEQUENCE AND COSTS

SEGMENT 1 Fryeburg to Brownfield

| Segment | Length (Mi.) | Trail Cost (\$) | | Mile Post | Bridge | Bridge Cost (\$) | Stream Crossing | Stream Crossing Cost (\$) | Pedestrian Crossing | Pedestrian Crossing Cost (\$) |
|--|--------------|-----------------|-------------|-----------|-------------------|------------------|-------------------|---------------------------|------------------------|-------------------------------|
| | | Paved | Stone Dust | | | | | | | |
| 1 | 3.47 | \$2,600,000 | \$1,800,000 | 46.83 | | | | | HAWK Signal @ Rte. 113 | \$150,000 |
| | | | | 46.71 | | | 4'X5' Granite Box | \$260,000 | | |
| | | | | 46.27 | Little Saco River | \$60,000 | | | | |
| | | | | 46.16 | | | 3'X5' Granite Box | \$250,000 | | |
| | | | | 45.35 | | | 2'X4' Granite Box | \$230,000 | | |
| | | | | 43.76 | Shepard's Brook | \$190,000 | | | | |
| Segment 1 Total Cost: (Paved)= \$3,740,000 (Stone Dust) = \$2,940,000 | | | | | | | | | | |

SEGMENT 2 Brownfield to Hiram

| | | | | | | | | | | |
|--|------|-------------|-------------|--|----------------|-----------|-----------------------------|-------|------------------------|-----------|
| 2 | 6.52 | \$4,900,000 | \$3,300,000 | 43.35 | | | | | RRFB @ Rte. 160 | \$20,000 |
| | | | | 42.95 | | | Twin 6' X 10' Granite Boxes | | | |
| | | | | 42.43 | | | 5'X6' Granite Box | | | |
| | | | | 41.06 | Ten Mile Brook | \$130,000 | | | | |
| | | | | 39.90 | | | Rattlesnake Pond | | | |
| | | | | 39.00 | | | | | HAWK Signal @ Rte. 113 | \$150,000 |
| | | | | 38.67 | Pierce's Brook | \$580,000 | | | | |
| | | | | 37.45 | Red Mill Brook | \$110,000 | | | | |
| | | | | 37.01 | Cattle Pass | \$60,000 | | | | |
| | | | | Proposed Trail Head @ Mountain View Ave. | | | | 36.84 | | \$53,000 |
| Segment 2 Total Cost: (Paved)= \$6,003,000 Stone Dust = \$4,403,000 | | | | | | | | | | |

CONSTRUCTION SEQUENCE AND COSTS

SEGMENT 3 Hiram to West Baldwin

| Segment | Length (Mi.) | Trail Cost (\$) | | Mile Post | Bridge | Bridge Cost (\$) | Stream Crossing | Stream Crossing Cost (\$) | Pedestrian Crossing | Pedestrian Crossing Cost (\$) |
|--|--------------|-----------------|-------------|-----------|------------------|------------------|-------------------|---------------------------|---------------------|-------------------------------|
| | | Paved | Stone Dust | | | | | | | |
| 3 | 5.20 | \$3,800,000 | \$2,600,000 | 36.32 | Saco River | \$390,000 | | | | |
| | | | | 35.41 | | | 4'X5' Granite Box | | | |
| | | | | 33.97 | Break Neck Brook | | | | | |
| | | | | 33.50 | | | 4'X6' Granite Box | | | |
| | | | | 33.04 | | | Unidentified | | | |
| | | | | 32.90 | Dug Hill Brook | \$290,000 | | | | |
| | | | | 32.19+/- | | | Unidentified | | | |
| Proposed Trail Head @ Route 5/117 | | | | 31.64 | \$98,000 | | | RRFB @ Rte. 5/117 | \$20,000 | |
| Segment 3 Total Cost: (Paved)= \$4,598,000 (Stone Dust) = \$3,398,000 | | | | | | | | | | |

SEGMENT 4 West Baldwin to Baldwin

| | | | | | | | | | | |
|--|------|-------------|-------------|----------|--------------|-----------|-------------------|-----|--|--|
| 4 | 5.15 | \$3,800,000 | \$2,600,000 | 30.39 | No Name | \$150,000 | | | | |
| | | | | 29.70 | Red Brook | \$150,000 | | | | |
| | | | | 29.30 | Pigeon Brook | - | | | | |
| | | | | 28.84 | | - | 6'x5' Granite Box | | | |
| | | | | 27.86+/- | | | Unidentified | | | |
| | | | | 27.18 | | - | 3'X3' Granite Box | | | |
| Proposed Trail Head @ Whistle Stop | | | | 26.49 | \$162,000 | | | N/A | | |
| Segment 4 Total Cost: (Paved)= \$4,262,000 (Stone Dust) = \$3,062,000 | | | | | | | | | | |

CONSTRUCTION SEQUENCE AND COSTS

SEGMENT 5
Baldwin to
Standish

SEGMENT 6
PWD
Segment

| Segment | Length (Mi.) | Trail Cost (\$) | | Mile Post | Bridge | Bridge Cost (\$) | Stream Crossing | Stream Crossing Cost (\$) | Pedestrian Crossing | Pedestrian Crossing Cost (\$) | | |
|--|-------------------|-----------------|-------------|-----------|--------------|------------------|--------------------------|---------------------------|------------------------|-------------------------------|----------|--|
| | | Paved | Stone Dust | | | | | | | | | |
| 5 | 6.05 | \$4,300,000 | \$2,900,000 | 26.04 | Quaker Brook | \$640,000 | | | | | | |
| | | | | 25.36 | | | 2.5'X4' Granite Box | | | | | |
| | | | | 24.89 | | | Twin 6'X4' Granite Boxes | | | | | |
| | | | | 24.73 | | | | | | RRFB @ Route 11 | \$20,000 | |
| | | | | 24.58 | | | | | | RRFB @ Rte. 113 | \$20,000 | |
| | | | | 22.99+/- | | | | | Twin Pipe Culvert | \$40,000 | | |
| | | | | 20.92+/- | | | | | Rich Millpond CMP | \$20,000 | | |
| Proposed Trail Head @ Route 114 | | | | 20.42 | | \$69,000 | | | HAWK Signal @ Rte. 114 | \$150,000 | | |
| Segment 5 Total Cost: (Paved)= \$5,259,000 (Stone Dust) = \$3,859,000 | | | | | | | | | | | | |
| 6 | ¹ 4.14 | \$6,300,000 | \$5,900,000 | N/A | | | | | RRFB @ Rte. 35 | \$20,000 | | |
| Segment 6 Total Cost: (Paved)= \$6,320,000 (Stone Dust) = \$5,920,000 | | | | | | | | | | | | |

¹ Length of Segment includes Alternative 1 through PWD land

PROGRAMMATIC COSTS & RECOMMENDATIONS

| Mountain Division Trail Programmatic Costs by Segment - Paved | | | | | | | |
|---|----------------|----------------|----------------|----------------|----------------|----------------|------------------------|
| | Segment 1 | Segment 2 | Segment 3 | Segment 4 | Segment 5 | Segment 6 | Total |
| Construction Costs | \$3,740,000.00 | \$6,003,000.00 | \$4,598,000.00 | \$4,262,000.00 | \$5,259,000.00 | \$6,320,000.00 | \$ 30,182,000.00 |
| Design (10% of construction) | \$ 374,000.00 | \$ 600,300.00 | \$ 459,800.00 | \$ 426,200.00 | \$ 525,900.00 | \$ 632,000.00 | \$ 3,018,200.00 |
| Construction Engineering (10% of construction) | \$ 374,000.00 | \$ 60,030.00 | \$ 45,980.00 | \$ 42,620.00 | \$ 52,590.00 | \$ 63,200.00 | \$ 301,820.00 |
| Right of Way | \$ - | \$ - | \$ - | \$ 5,000.00 | \$ - | \$ 20,000.00 | \$ - |
| Environmental | | | | | | | |
| Total Programmatic Costs | | | | | | | \$33,502,020.00 |

| Mountain Division Trail Programmatic Costs by Segment - Stone Dust | | | | | | | |
|--|----------------|----------------|----------------|----------------|----------------|----------------|------------------------|
| | Segment 1 | Segment 2 | Segment 3 | Segment 4 | Segment 5 | Segment 6 | Total |
| Construction Costs | \$2,940,000.00 | \$4,403,000.00 | \$3,398,000.00 | \$3,062,000.00 | \$3,859,000.00 | \$5,920,000.00 | \$ 23,582,000.00 |
| Design (10% of construction) | \$ 294,000.00 | \$ 440,300.00 | \$ 339,800.00 | \$ 306,200.00 | \$ 385,900.00 | \$ 592,000.00 | \$ 2,358,200.00 |
| Construction Engineering (10% of construction) | \$ 294,000.00 | \$ 44,030.00 | \$ 33,980.00 | \$ 30,620.00 | \$ 38,590.00 | \$ 59,200.00 | \$ 235,820.00 |
| Right of Way | \$ - | \$ - | \$ - | \$ 5,000.00 | \$ - | \$ 20,000.00 | \$ - |
| Environmental | | | | | | | |
| Total Programmatic Costs | | | | | | | \$26,176,020.00 |

PROGRAMMATIC COSTS & RECOMMENDATIONS

Recommendations

- Construct Segment 1 (Fryeburg to Brownfield) first since it is an extension of an existing facility; is the least expensive segment; and provides connectivity to residential areas in Brownfield.
- Begin design of Segment 6 (PWD property) shortly after Segment 1 to allow coordination efforts to take place possibly allowing this segment to be constructed next, creating more connectivity to existing trails.
- Segments 2, 3, 4, & 5 to follow based on funding.



(207) 592-3384



mainedot.gov



Dakota.Hewlett@maine.gov

Dakota Hewlett

Project Manager

Active Transportation Planner

Bicycle and Pedestrian Funding Program

Manager

Contact Dakota

Leave this area blank for video
narration